



**New Jersey Department of Transportation
FY 2009-2018 STIP Addendum
American Recovery and Reinvestment Act
State and Local Projects
(\$ in Millions)**



State Route #	Project	MP to MP	Description	Total Cost (in millions)	ARRA Programmed Federal Share	ARRA Fund Category	Phase of Work	SCIS Category	Municipalities	County	STIP Reference #	MPO
<u>NJDOT State Highway Projects</u>												
1	Rt 1, Vicinity of D&R Canal to North of CR 533, Resurfacing	6.48 to 8.5	The purpose of the project is to extend the usable life of the highway by milling 3" and resurfacing with 3' of pavement. Existing underclearances will be maintained.	\$10.000	\$10.000	ARRA - STP Flex	Construction	Road Asset	Lawrence Twp., West Windsor Twp.	Mercer	09309	DVRPC
4	Rt. 4 over Flat Rock Brook	9.55 to 9.75	Design work. Will accelerate the final design work for bridge deck replacement allowing construction phase to begin sooner.	\$0.800	\$0.800	ARRA - STP Flex	Design	Bridge Asset	Englewood City	Bergen	93136	NJTPA
7	Rt 7 Hackensack River Wittpenn BR Contract 3	0.2 to 0.5	Design work. Accelerates the completion of final design which will allow for construction phase of project to begin sooner. The future construction phase will allow for a Rt. 7 project (Contract 3 of 4) to provide for the new vertical lift span over the Hackensack River. The new bridge will be located approximately 200 feet north of the existing bridge.	\$4.500	\$4.500	ARRA - STP - NJ	Design	Bridge Asset	Jersey City, Kearny	Hudson	075C	NJTPA
7	Rt 7 Hackensack River Wittpenn BR Contract 4	0.0 to 0.6	Design work. Accelerates the completion of final design which will allow for construction phase of project to begin sooner. The future construction phase will allow for a Rt. 7 project (Contract 4 of 4) provides for the final bridge & approach roadway segments of the new vertical lift bridge over the Hackensack R. & the improvements to the interchange at Fish House Rd. New connection ramps to Newark Ave & St. Paul's A.	\$8.500	\$8.500	ARRA - STP - NJ	Design	Bridge Asset	Jersey City, Kearny	Hudson	075D	NJTPA
10	CR 665 (Salem St.) over Rt. 10	16.35	Design work. Will accelerate the final design work for bridge deck replacement allowing construction phase to begin sooner.	\$0.700	\$0.700	ARRA - STP Flex	Design	Bridge Asset	Randolph Twp.	Morris	03304	NJTPA
17	Ramapo Avenue (CR 100) over Rt 17	25.6	Ramapo Ave Bridge over Rt17 requires partial deck replacement. Also included is re-profiling of the deck and roadway approaches to improve drainage, reconstruction of deteriorated concrete abutment headers, and patching of spalls.	\$1.900	\$1.900	ARRA - STP Flex	Construction	Bridge Asset	Mahwah Twp.	Bergen	03304	NJTPA
18	Rt.18 Over Rt. 1	40.61	Design work. Will accelerate the final design work for bridge deck replacement allowing construction phase to begin sooner.	\$1.000	\$1.000	ARRA - STP Flex	Design	Bridge Asset	New Brunswick City	Middlesex	03304	NJTPA
18 95	Median Crossover Crash Prevention Contract #10	Various	Contract # 10 will protect about 5.14 miles of Route 18, from MP 16.56 to MP 19.20, MP 24.30 to MP 25.2; and MP 28.70 to MP 30.70; and 4.64 miles of Route I-95, from MP 0.55 to MP 2.22 and from MP 5.8 to MP 8.77 where cross median accidents have occurred.	\$4.000	\$4.000	ARRA - STP Flex	Construction	Safety Asset	Mercer County: Ewing Twp.; Lawrence Twp.; Monmouth County: Colts Neck Twp.; Marlboro Twp.; Middlesex County: Old Bridge	Mercer, Middlesex, Monmouth	03316	NJTPA/ DVRPC
24 280	Median Crossover Crash Prevention Contract #11	Various	Projects will protect about 5.05 miles of Route 24, from MP 1.35 to MP 1.6, MP 1.82 to MP 5.0; and MP 5.2 to MP 6.82 and 3.77 miles of Route I-280, from MP 1.1 to MP 1.7 and from MP 2.3 to MP 3.2, and MP 5.2 to MP 7.47 where cross median accidents have occurred.	\$3.500	\$3.500	ARRA - STP Flex	Construction	Safety Asset	Essex County: Millburn; Roseland; Livingston; West Orange; Morris County: East Hanover; Chatham; Morris Twp.; Hanover; Florham Park; Madison; Parsippany-Troy Hills	Essex, Morris	03316	NJTPA
29	Rt 29 West Amwell Twp Drainage (Sheet Flow)	17.1 to 18.12	The project involves roadway & drainage improvements on Route 29 in West Amwell Township & City of Lambertville. The project includes pavement resurfacing and drainage upgrades.	\$2.200	\$2.200	ARRA - STP Flex	Construction	Road Asset	West Amwell Twp., Lambertville City	Hunterdon	93166	DVRPC
30	Rt 30 Cooper River Drainage Improvement	1.5 to 3.15	This project will relieve flooding on Rt. 30 with the construction of inlets, pipes, detention basins and outfalls. In addition milling and resurfacing of a portion of Rt 30 eastbound is included.	\$13.000	\$13.000	ARRA - STP Flex	Construction	Road Asset	Camden City; Pennsauken Twp.	Camden	9377	DVRPC
30	Rt 30, Pavement Rehabilitation, Atlantic County	32.0 to 36.4	Project provides roadway resurfacing.	\$5.900	\$6.000	ARRA - STP Flex	Construction	Road Asset	Hammonton; Mullica Twp.	Atlantic	09311	SJTPO
35	Rt 35 Restoration Berkley Twp to Toms River	0.0 to 4.0	Design work. Allows for the completion of final design. Completing final design will allow the construction phase to begin sooner for pavement restoration and drainage improvements on Route 35 from milepost 0.0 to 4.0.	\$1.000	\$1.000	ARRA - STP - NJ	Design	Road Asset	Berkeley Twp.; Seaside Heights Boro; Seaside Park; Toms River Twp.	Ocean	9147A	NJTPA
35	Rt 35 Restoration Toms River Twp to Mantoloking	4.0 to 9.0	Design work. Allows for the completion of final design. Completing final design will allow the construction phase to begin sooner for pavement restoration and drainage improvements on Route 35 from milepost 4.0 to 9.0.	\$1.000	\$1.000	ARRA - STP - NJ	Design	Road Asset	Toms River Twp.; Lavallette Boro; Brick Twp.; Mantoloking Boro	Ocean	9147C	NJTPA
46	Roff Avenue over Rt 46	71.96	Bridge superstructure replacement. Roff Avenue goes over Rt. 46.	\$2.500	\$2.500	ARRA - STP Flex	Construction	Bridge Asset	Palisades Park Boro	Bergen	03304	NJTPA



**New Jersey Department of Transportation
FY 2009-2018 STIP Addendum
American Recovery and Reinvestment Act
State and Local Projects
(\$ in Millions)**



State Route #	Project	MP to MP	Description	Total Cost (in millions)	ARRA Programmed Federal Share	ARRA Fund Category	Phase of Work	SCIS Category	Municipalities	County	STIP Reference #	MPO
46	Rt 46 & Main Street 0220515	66.35 to 66.77	This project includes major roadway and drainage improvements at the intersection of Rt. 46 and Main Street in the Borough of Lodi, Bergen County; two bridge replacements and provide auxiliary lanes.	\$47.600	\$48.600	ARRA - STP Flex	Construction	Congestion Relief	Lodi Boro	Bergen	93281	NJTPA
46	Grove Street (CR 623) over Rt 46	61.09	This project consists of superstructure replacement over Route 46 in Clifton City, Passaic County. There will be cast in place concrete deck with new pier caps and bearings that will improve a bridge deck seat. Also included is some substructure repairs.	\$4.700	\$4.700	ARRA - STP Flex	Construction	Bridge Asset	Clifton City	Passaic	03304	NJTPA
52	Rt 52 Causeway Replace & Somers Pt Circle Elim Cont B 0511514	1.65 to 2.74	Rt. 52 Causeway Replacement and Somers Point Circle Elimination, Contract B. This project replaces the two bascule bridges located closest to Somers Point and Ocean City at Ship Channel and Beach Thorofare, respectively, with high level fixed spans.	\$298.900	\$70.000	ARRA - STP Flex	Construction	Bridge Asset	Atlantic County: Somers Point City, Cape May County: Ocean City	Atlantic; Cape May	244A	SJTPO
72	Rt 72, Manahawkin Bay Bridge Deck Rehabilitation	26.1 to 28.25	The project involves deck repair, curb repair and applying deck overlay system on the entire deck of Rt.72 Over Manhawkin Bay bridge.	\$12.000	\$12.000	ARRA - STP Flex	Construction	Bridge Asset	Stafford Twp	Ocean	03304	NJTPA
78	I-78 Ramp A over I-78	18.83	Design work. Will accelerate the final design work for bridge deck replacement allowing construction phase to begin sooner.	\$0.700	\$0.700	ARRA - STP Flex	Design	Bridge Asset	Clinton Twp.	Hunterdon	03304	NJTPA
78	I-78, Corridor Bridge Painting	Various	Addresses painting needs for 9 bridges along the I-78 corridor. A list of bridges include in this corridor is included.	\$6.000	\$6.000	ARRA - STP Flex	Construction	Bridge Asset	Essex County: Newark; Hunterdon County: Bloomsbury; Union Twp.; Somerset County: Bedminster; Union County: Springfield Twp.	Essex, Hunterdon, Somerset, Union	X08	NJTPA
78	I-78, Eastbound Roadway Rehabilitation	4.16 to 4.7	Pavement Resurfacing Project	\$3.500	\$3.500	ARRA - STP Flex	Construction	Road Asset	Greenwich Twp.	Warren	FS09392	NJTPA
78	I-78, Union/Essex Rehabilitation, Contract C	57.0 to 58.43	The purpose of the project is to perform preventive repairs and safety improvements to this section of I-78. This includes rubblization and overlay of the existing pavement, reconstruction of existing concrete pavement drainage improvements.	\$25.000	\$25.000	ARRA - STP Flex	Construction	Road Asset	Newark City	Essex	00373C	NJTPA
80	I-80 East Bound West of Madison Ave to Polify Rd Resurfacing 1610517	58.9 to 65.4	This project will mill and resurface this section of I-80 between M.P. 58.9-65.4. There will be some deck patching performed. Guide rail upgrades will be included.	\$14.000	\$15.000	ARRA - STP Flex	Construction	Road Asset	Passaic County: Paterson City; Bergen County: Elmwood Park Boro; Saddle Brook Twp; Lodi; Hackensack	Bergen, Passaic	07310	NJTPA
80	I-80 EB & WB over Berkshire Valley Road	31.99	This project involves Route I-80 (Milepost 31.99) bridge deck replacement over Berkshire Valley Road. Also, due to severe spalls, bridge piers will be repaired.	\$9.200	\$9.200	ARRA - STP Flex	Construction	Bridge Asset	Roxbury Twp.	Morris	03304	NJTPA
80	I-80 Westbound East of South Beverwyck Rd to W of Rt 23 Intchg 2204857	45.6 to 53.3	This is a resurfacing project consists of milling 2" and repaved with 5" of Superpave Hot Mix Asphalt. Substandard guide rail will be upgraded. Existing vertical under-clearances will be maintained at all underpasses.	\$13.000	\$14.000	ARRA - STP Flex	Construction	Road Asset	Essex County: Fairfield Twp.; Morris County: Parsippany-Troy Hills Twp.; Montville; Passaic County: Wayne Twp.	Essex, Morris, Passaic	07311	NJTPA
80	I-80, Corridor Bridge Painting	Various	Addresses painting needs for 20 bridges along the I-80 corridor. A list of bridges in this corridor is included.	\$10.000	\$10.000	ARRA - STP Flex	Construction	Bridge Asset	Bergen County: Hackensack; South Hackensack; Saddle Brook; Elmwood Park; Fort Lee; Essex County: Fairfield; Morris County: Parsippany-Troy Hills; Passaic County: Paterson; Warren County: Allamuchy; Blairstown	Bergen, Essex, Morris, Passaic, Warren	X08	NJTPA
159	Rt 159 WB over Rt 46 EB	1.31	This is a bridge superstructure replacement project that is one of the economic stimulus projects. The project will replace the superstructure of Rt. 159 Westbound over Rt. 46 Eastbound. Vertical underclearance will be improved for Rt. 46 Eastbound.	\$1.800	\$1.800	ARRA - STP Flex	Construction	Bridge Asset	Montville Twp.	Morris	03304	NJTPA
206	Main Street (CR 543) over Rt 206	30.64	Deck replacement with minor Abutment repairs on Burlington County Route 543 in the Town of Columbus, Mansfield Township, Burlington County.	\$1.900	\$1.900	ARRA - STP Flex	Construction	Bridge Asset	Mansfield Twp.	Burlington	03304	DVRPC
280	I-280, Corridor Bridge Painting 2204861	Various	Addresses painting needs for 49 bridges along the I-280 corridor. A list of bridges in this corridor is included.	\$15.300	\$15.300	ARRA - STP Flex	Construction	Bridge Asset	East Orange; Newark; Orange; West Orange	Essex	X08	NJTPA



New Jersey Department of Transportation
FY 2009-2018 STIP Addendum
American Recovery and Reinvestment Act
State and Local Projects
 (\$ in Millions)



State Route #	Project	MP to MP	Description	Total Cost (in millions)	ARRA Programmed Federal Share	ARRA Fund Category	Phase of Work	SCIS Category	Municipalities	County	STIP Reference #	MPO
287	I-287 NB over Rt 46, Deck Rehabilitation	42.47	The project will construct improvements to restore the deck of the north bound structure. Improvements will consist of rehabilitation that includes partial depth deck replacement and deck sealing over the entire length of the bridge.	\$3.100	\$3.100	ARRA - STP Flex	Construction	Bridge Asset	Parsippany-Troy Hills Twp.	Morris	03304	NJTPA
287	I-287 Vicinity of Stelton Road to Vicinity of Main St, Resurfacing	5.9 to 12.9	The project consist of milling and resurfacing and upgrading guide rail will be upgraded to meet existing standards as necessary. Two deck replacement and one superstructure replacement.	\$37.000	\$40.000	ARRA - STP Flex	Construction	Road Asset	Middlesex County: Piscataway Twp.; Somerset County: Franklin Twp.; Bridgewater Twp.	Middlesex, Somerset	07307	NJTPA
295	I-295 Gloucester/Camden Rehabilitation, Rt 45 to Berlin-Haddonfield Road 0427507	24.53 to 32.4	I-295 pavement rehabilitation from Route 45 (Interchange 24) to Berlin-Haddonfield Rd (CR 561) (Interchange 32) Milepost 24.5- 32.4; includes bridge deck replacements on 4 mainline structures.	\$80.000	\$84.000	ARRA - STP Flex	Construction	Road Asset	Gloucester County: West Deptford Twp.; Deptford; Westville; Camden County: Bellmawr; Haddon Heights Boro; Barrington; Lawnside; Tavistock, Haddonfield, Cherry Hill Twp.	Camden; Gloucester	00372	DVRPC
295	I-295, Corridor Bridge Painting	Various	Addresses painting needs for 10 bridges along the I-295 corridor. A list of bridges in this corridor is included.	\$6.000	\$6.000	ARRA - STP Flex	Construction	Bridge Asset	Salem County: Carneys Point Twp.; Gloucester County: Logan Twp.	Gloucester, Salem	X08	DVRPC/SJTPO
440	Rt. 440 Ramp V/Boggs St., West Side Ave., State St. & NJ TRANSIT	4.03 to 4.24	Design work. Will accelerate the final design work for bridge deck replacement allowing construction phase to begin sooner.	\$0.800	\$0.800	ARRA - STP Flex	Design	Bridge Asset	Perth Amboy City	Middlesex	03304	NJTPA
440	Rt 440, JFK Blvd. to 22nd St, Resurfacing	18.9 to 20.3	Project will provide for resurfacing along project limits.	\$4.000	\$4.000	ARRA - STP Flex	Construction	Road Asset	Bayonne City	Hudson	09308	NJTPA
440	Rt 440, Ramp WK over Woodbridge Avenue (CR 514)	0.42	Replace the bridge deck carrying Rt 440 NB over Ramp WI and the deck carrying Ramp WK over CR 514. Both bridges are within the interchange of RT 440, CR 514 and NJTA exit 10.	\$3.800	\$3.800	ARRA - STP Flex	Construction	Bridge Asset	Edison Twp.	Middlesex	03304	NJTPA
440	Smith Road (CR 656) over Rt 440, Ramp "GW"	1.46	Provides for new bridge deck construction.	\$3.100	\$3.100	ARRA - STP Flex	Construction	Bridge Asset	Woodbridge Twp.	Middlesex	03304	NJTPA
1&9T	Rt. 1&9T Moveable Bridge Painting 2204802	Various	Provides for necessary painting for 2 moveable bridges over the Hackensack and Passaic Rivers.	\$30.000	\$34.000	ARRA - STP Flex	Construction	Bridge Asset	Essex County: Newark; Hudson County: Jersey City, Kearny	Essex, Hudson	X08	NJTPA
295/76/42	I-295 & 42/I-76 Direct Connection Camden County	25.71 to 28.2	Right -of-Way acquisition only. Funding will accelerate the purchase of the necessary Right of Way required for future construction phases of the project. The future construction phase proposes construction of a new alignment to carry I-295 mainline through the interchange. The existing interchange does not provide a direct connection for I-295 thru traffic.	\$19.000	\$7.000	ARRA - STP Flex	Right of Way	Congestion Relief	Gloucester City, Bellmawr Boro, Mount Ephraim Boro	Camden	355	DVRPC



New Jersey Department of Transportation
FY 2009-2018 STIP Addendum
American Recovery and Reinvestment Act
State and Local Projects
 (\$ in Millions)



State Route #	Project	MP to MP	Description	Total Cost (in millions)	ARRA Programmed Federal Share	ARRA Fund Category	Phase of Work	SCIS Category	Municipalities	County	STIP Reference #	MPO
<u>Transportation Enhancements</u>												
	Transportation Enhancements	Various	This program provides federal funding for projects such as scenic enhancements, historic preservation, and bicycle and pedestrian improvements	\$16.103	\$16.103	ARRA - STP-TE	ERC	Local System Support	Statewide	Statewide	X107	NJTPA DVRPC SJTPO
	Hudson River Waterfront Walkway (Weehawken Cove) Hoboken and Weehawken, Hudson County	NA	<p>This project will provide for construction of approximately 800 feet of walkway along the Hudson River waterfront at Weehawken Cove.</p> <p>This project was previously authorized in the amount of \$1,879,000 of TCSP funds. This authorization was rescinded due to lack of billing. The funds will have to be authorized again in 2007. This project is also subject to an FY 2006 appropriation in the amount of \$750,000.</p>	\$1.900	\$1.900	ARRA - STP-TE	Construction	Local System Support	Hoboken City Weehawken Twp.	Hudson	HP01012	NJTPA
	Castle Point Walkway, Hudson County	NA	<p>This project will provide for the construction of the continuation of the Hudson River Waterfront Walkway in Hoboken in front of Stevens Institute. The project is sponsored by NJ Department of Environmental Protection in conjunction with Stevens Institute.</p> <p>The following special Federal appropriation was allocated to this project. SAFETEA-LU, \$800,000 (available 20% per year), and FY06 Appropriation Bill (\$0.75 million).</p>	\$1.550	\$1.550	ARRA - STP-TE	Construction	Local System Support	Hoboken City	Hudson	06342	NJTPA



New Jersey Department of Transportation
FY 2009-2018 STIP Addendum
American Recovery and Reinvestment Act
State and Local Projects
 (\$ in Millions)



State Route #	Project	MP to MP	Description	Total Cost (in millions)	ARRA Programmed Federal Share	ARRA Fund Category	Phase of Work	SCIS Category	Municipalities	County	STIP Reference #	MPO
---------------	---------	----------	-------------	--------------------------	-------------------------------	--------------------	---------------	---------------	----------------	--------	------------------	-----

Local Projects by MPO Region

SJTPO Local Projects

	Ocean Drive (CR619) Bridge over Townsends Inlet Recoating Steelwork	10.6 to 10.8	Bridge Painting	\$2.150	\$2.150	ARRA - STP-SJ	Construction	Local System Support	Avalon and Sea Isle City	Cape May	FSS09525	SJTPO
	Ocean Drive (CR619) Bridge over Grassy Sound Recoating Steelwork	0.4 to 0.6	Bridge Painting	\$1.800	\$1.800	ARRA - STP-SJ	Construction	Local System Support	Middle Township	Cape May	FSS09526	SJTPO
	C.R. 552 (Irving Avenue)	3.8 to 6.0	Mill and Overlay existing pavement	\$0.275	\$0.275	ARRA - STP-SJ	Construction	Local System Support	Deerfield Township	Cumberland	FSS09529	SJTPO
	C.R. 552 (Sherman Avenue)	6.0 to 7.75	Mill and Overlay existing pavement and upgrade existing guiderail	\$0.225	\$0.225	ARRA - STP-SJ	Construction	Local System Support	City of Millville	Cumberland	FSS09530	SJTPO
	C.R.607 (West Avenue)	6.24 to 7.38	Mill and Overlay existing pavement	\$0.600	\$0.600	ARRA - STP-SJ	Construction	Local System Support	Bridgeton	Cumberland	FSS09538	SJTPO
	C.R.621 (West Park Drive)	2.16 to 6.27	Mill and Overlay existing pavement, raised pavement markers and upgrade existing guiderail	\$0.300	\$0.300	ARRA - STP-SJ	Construction	Local System Support	Bridgeton and Upper Deerfield Twp	Cumberland	FSS09540	SJTPO
	C.R.555 (Wheaton Avenue)	10.8 to 11.3	Mill and Overlay existing pavement	\$0.150	\$0.150	ARRA - STP-SJ	Construction	Local System Support	City of Millville	Cumberland	FSS09536	SJTPO
	C.R.622 (Cornwell Drive)	0.62 to 1.17	Mill and Overlay existing pavement, long life pavement markings and upgrade existing guiderail	\$0.150	\$0.150	ARRA - STP-SJ	Construction	Local System Support	Upper Deerfield Twp	Cumberland	FSS09541	SJTPO
	C.R.678 (Wade Boulevard)	0.00 to 1.32	Mill and Overlay existing pavement	\$0.650	\$0.650	ARRA - STP-SJ	Construction	Local System Support	City of Millville	Cumberland	FSS09549	SJTPO
	S. East Avenue, Chestnut Ave. to Landis Ave.	N/A	Rehab of existing concrete road joint repair, curb & gutter repair, and bituminous overlay.	\$1.069	\$1.069	ARRA - STP-SJ	Construction	Local System Support	Vineland	Cumberland	FSS09553	SJTPO
	CR 667 Harmersville - Pecks Corner Rd	2.6 to 4.6	Resurfacing and various safety improvements	\$0.838	\$0.838	ARRA - STP-SJ	Construction	Local System Support	Quinton and Lower Alloway Creek	Salem	FSS09556	SJTPO



**New Jersey Department of Transportation
FY 2009-2018 STIP Addendum
American Recovery and Reinvestment Act
State and Local Projects
(\$ in Millions)**



State Route #	Project	MP to MP	Description	Total Cost (in millions)	ARRA Programmed Federal Share	ARRA Fund Category	Phase of Work	SCIS Category	Municipalities	County	STIP Reference #	MPO
	DVRPC Local Projects											
	BurlCo Resurface Marne Highway (CR 537) from Hartford Road to Mt. Holly Bypass	12.86-17.62	2" of surface course and resurfacing the milled area by 2" thick asphalt. All work will be done within the existing county Right of way. The relocation of the existing utilities will not be required. Also, the milling and resurfacing will occur within the existing pavement.	\$1.343	\$1.343	ARRA - STP-STU	Construction	Local System Support	Mt. Laurel and Hainesport	Burlington	FSD09483	DVRPC
	BurlCo Resurface Old York Road (CR660) from CR 543 to CR 678 and from CR 545 to CR 677	2.75 and 9.77 12.1	2" of surface course and resurfacing the milled area by 2" thick asphalt. All work will be done within the existing county Right of way. The relocation of the existing utilities will not be required. Also, the milling and resurfacing will occur within the existing pavement.	\$0.825	\$0.825	ARRA - STP-STU	Construction	Local System Support	Florence, Mansfield, and Chesterfield	Burlington	FSD09484	DVRPC
	BurlCo Resurface Jacksonville-Hedding Road (CR 628) from CR 660 to 543	7.68-5.45	2" of surface course and resurfacing the milled area by 2" thick asphalt. All work will be done within the existing county Right of way. The relocation of the existing utilities will not be required. Also, the milling and resurfacing will occur within the existing pavement.	\$0.332	\$0.332	ARRA - STP-STU	Construction	Local System Support	Mansfield	Burlington	FSD09485	DVRPC
	BurlCo Medford Township and Medford Lakes Borough Traffic Signal Upgrade & Coordination CR 541	7.37-10.5	Coordinate and upgrade existing signalized intersections on CR 541/Stokes Road in Medford Township and Medford Lakes Borough. 8 existing signalized intersections will be upgraded and coordinated with the existing Signal Coordination System in the County and operated from the County's Traffic Operations Center. Provide traffic signal coordination for improved vehicle progression. Detect and report traffic signal malfunctions. Automatically collect and archive traffic data. CCTV Cameras for incident management. Local intersection safety upgrades including left turn and pedestrian phasing.	\$1.500	\$1.500	ARRA - STP-STU	Construction	Local System Support	Medford Township and Medford Lakes Borough	Burlington	FSD09486	DVRPC
	BurlCo Traffic Signal Upgrade & Coordination (Burlington, Westhampton, & Willingboro Twps.)	0-3.30	Coordination of fifteen intersections on Sunset Road, Levitt Parkway, and JFK Way. This existing system uses radio frequencies and will replace them with fiber optics. Coordinate and upgrade the traffic signals along Sunset Road, Levitt Parkway, and JFK Way in Burlington Township and Willingboro Township. This includes 15 existing signalized intersections that would be coordinated and added to the existing Traffic Signal Coordination System. Provide traffic signal coordination for improved vehicle progression. Detect and report traffic signal malfunctions. Automatically collect and archive traffic data. CCTV Cameras for incident management. Local intersection safety upgrades including left turn and pedestrian phasing.	\$4.000	\$4.000	ARRA - STP-STU	Construction	Local System Support	Burlington, Westhampton, and Willingboro	Burlington	FSD09487	DVRPC
	GlouCo - CR 555 Tuckahoe Road from Route 322 to Main Road in Franklin & Monroe Townships.	31.3-25.8	The project will consist of milling 2.5" of existing roadway and resurfacing to restore milled pavement along CR 555 Tuckahoe Road from Hewitt Rd. to Main Rd. in Franklin & Monroe Twps.	\$4.125	\$4.125	ARRA - STP-STU	Construction	Local System Support	Franklin & Monroe	Gloucester	FSD09489	DVRPC
	GlouCo - CR655 Fries Mill Road from Rt. 322 to CR 610 in Clayton & Monroe Townships.	3.7-6.2	The project will consist of milling 2.5" of existing roadway and resurfacing to restore milled pavement along CR 655 Fries Mill Rd. from Rt. 322 to CR 610 in Clayton & Monroe Twps.	\$1.750	\$1.750	ARRA - STP-STU	Construction	Local System Support	Clayton & Monroe	Gloucester	FSD09490	DVRPC
	GlouCo - CR 536 (aka Rt. 322) from CR 623 to CR618 in Harrison Township.	12.4-14.4	The project will consist of milling 2.5" of existing roadway and resurfacing to restore milled pavement along CR 536 (aka Rt. 322) from CR 623 to CR 618 in Harrison Twp.	\$1.500	\$1.500	ARRA - STP-STU	Construction	Local System Support	Harrison	Gloucester	FSD09491	DVRPC



**New Jersey Department of Transportation
 FY 2009-2018 STIP Addendum
 American Recovery and Reinvestment Act
 State and Local Projects
 (\$ in Millions)**



State Route #	Project	MP to MP	Description	Total Cost (in millions)	ARRA Programmed Federal Share	ARRA Fund Category	Phase of Work	SCIS Category	Municipalities	County	STIP Reference #	MPO
	GlouCo - CR 553 Woodbury Glassboro Road from CR639 to Bethel Mill Road in the Borough of Pitman.	42.7-43.2	The project will consist of milling 2.5" of existing roadway and resurfacing to restore milled pavement along CR 553 Woodbury-Glassboro Rd. from CR 639to Bethel Mill Road in the Borough of Pitman.	\$0.525	\$0.525	ARRA - STP-STU	Construction	Local System Support	Pitman	Gloucester	FSD09492	DVRPC
	GlouCo - CR655 Fries Mill Road from CR 689 to Rt. 322 in Washington & Monroe Townships.	10.7-12.2	The project will consist of milling 2.5" of existing roadway and resurfacing to restore milled pavement along CR 655 Fries Mill Rd. from CR 689 to Rte. 322 in Washington & Monroe Twps.	\$0.800	\$0.800	ARRA - STP-STU	Construction	Local System Support	Washington & Monroe	Gloucester	FSD09493	DVRPC
	GlouCo - Signalization of South Main Street (Route 45) and Mullica Road (Old Route 322)	17-17.6	Construction of a traffic signal at the intersection of South Main Street with Mullica Road (aka Old Mill intersection), pedestrian crossing and firehouse preemption to help alleviate congestion and safety at the intersection. Stop bars will be offset to allow for truck movements and new curb ramps and pedestrian facilities will be constructed. The project will also mill & overlay Rte. 45 on approaches to new signal.	\$0.400	\$0.400	ARRA - STP-STU	Construction	Local System Support	Harrison	Gloucester	FSD09495	DVRPC
	GlouCo - Countywide Upgrade of Pedestrian Crosswalk Facilities	Various	Gloucester County maintains over 100 traffic signals on over 400 miles of roadway. The County is requesting funding for the installation of pedestrian traffic signal countdown timers on all traffic signals that have not yet been retrofitted. The project would replace the existing old style standard WALK and DON'T WALK as well as the standard symbol HAND and WALKMAN pedestrian signals with the pedestrian countdown timers.	\$0.850	\$0.850	ARRA - STP-STU	Construction	Local System Support	Various	Gloucester	FSD09496	DVRPC
	MercerCo - Olden Avenue (CR622) Safety Improvements	Various	Remove traffic signal equipment from median islands at three intersection on Olden Avenue, Ewing Township. Project also includes pedestrian safety enhancements as well as traffic signal operations improvements.	\$0.300	\$0.300	ARRA - STP-STU	Construction	Local System Support	Ewing Twp	Mercer	FSD09497	DVRPC
	MercerCo - Pedestrian Count Down Replacements	Various	Replace existing pedestrian indications with Countdown pedestrian indications at 130 intersections.	\$0.200	\$0.200	ARRA - STP-STU	Construction	Local System Support	Various	Mercer	FSD09499	DVRPC
	MecerCo - Pedestrian Push Button Replacements	Various	Replace existing pedestrian push buttons with ADA compatible push buttons with user feedback at 130 intersections.	\$0.400	\$0.400	ARRA - STP-STU	Construction	Local System Support	Various	Mercer	FSD09500	DVRPC
	Mercer Pavement -Quaker Bridge Rd from Village to Hughes Dr	5.91-6.58	The project will consist of milling 2-3" from the existing roadway surface and resurfacing to restore pavement	\$0.528	\$0.528	ARRA - STP-STU	Construction	Local System Support	Hamilton and Lawrence	Mercer	FSD09503	DVRPC
	Mercer Pavement -Princeton Hightstown Rd from Clarksville to Slayback	39.50-40.32	The project will consist of milling 2-3" from the existing roadway surface and resurfacing to restore pavement	\$0.418	\$0.418	ARRA - STP-STU	Construction	Local System Support	West Windsor	Mercer	FSD09504	DVRPC
	Mercer Pavement -North Olden Ave from Parkside Ave to Prospect St.	4.96-5.32	The project will consist of milling 2-3" from the existing roadway surface and resurfacing to restore pavement	\$0.325	\$0.325	ARRA - STP-STU	Construction	Local System Support	Ewing Twp	Mercer	FSD09505	DVRPC
	Mercer Pavement -Princeton Ave from Spruce St to Olden Ave	44.54-44.67	The project will consist of milling 2-3" from the existing roadway surface and resurfacing to restore pavement	\$0.100	\$0.100	ARRA - STP-STU	Construction	Local System Support	Ewing and Trenton	Mercer	FSD09506	DVRPC
	Mercer Pavement -Whitehorse Ave from Kuser Rd to Olden Ave	1.16-1.41	The project will consist of milling 2-3" from the existing roadway surface and resurfacing to restore pavement	\$0.180	\$0.180	ARRA - STP-STU	Construction	Local System Support	Hamilton	Mercer	FSD09507	DVRPC
	Mercer Pavement -Arena Drive from Olden Ave to Rt. 295	1.48-2.13	The project will consist of milling 2-3" from the existing roadway surface and resurfacing to restore pavement	\$0.462	\$0.462	ARRA - STP-STU	Construction	Local System Support	Hamilton	Mercer	FSD09508	DVRPC
	Mercer Pavement -Clarksville Rd from Everett Drive to North Post Road	2.56-2.65	The project will consist of milling 2-3" from the existing roadway surface and resurfacing to restore pavement	\$0.140	\$0.140	ARRA - STP-STU	Construction	Local System Support	West Windsor	Mercer	FSD09509	DVRPC
	Mercer Pavement -Nottingham Way from Rt 33 to 5 Points	0.00-0.13	The project will consist of milling 2-3" from the existing roadway surface and resurfacing to restore pavement	\$0.176	\$0.176	ARRA - STP-STU	Construction	Local System Support	Hamilton	Mercer	FSD09510	DVRPC



New Jersey Department of Transportation
FY 2009-2018 STIP Addendum
American Recovery and Reinvestment Act
State and Local Projects
 (\$ in Millions)



State Route #	Project	MP to MP	Description	Total Cost (in millions)	ARRA Programmed Federal Share	ARRA Fund Category	Phase of Work	SCIS Category	Municipalities	County	STIP Reference #	MPO
	Mercer Pavement -Robbinsville- Allentown Rd from Vahlsing Way to Rt 130	7.02-7.66	The project will consist of milling 2-3" from the existing roadway surface and resurfacing to restore pavement	\$0.175	\$0.175	ARRA - STP-STU	Construction	Local System Support	Robbinsville	Mercer	FSD09511	DVRPC
	Mercer Pavement -W Broad St from Greenwood to Louellen	10-10.3	The project will consist of milling 2-3" from the existing roadway surface and resurfacing to restore pavement	\$0.140	\$0.140	ARRA - STP-STU	Construction	Local System Support	Hopewell Borough	Mercer	FSD09512	DVRPC
	Mercer Pavement -West Upper Ferry from Grand Ave to River Road	0-1.17	The project will consist of milling 2-3" from the existing roadway surface and resurfacing to restore pavement	\$0.451	\$0.451	ARRA - STP-STU	Construction	Local System Support	Ewing	Mercer	FSD09513	DVRPC
	Mercer Pavement -E State St from Chambers St to Olden Ave	0.46-0.94	The project will consist of milling 2-3" from the existing roadway surface and resurfacing to restore pavement	\$0.200	\$0.200	ARRA - STP-STU	Construction	Local System Support	Trenton	Mercer	FSD09514	DVRPC
	Mercer Pavement -Olden Ave from Clinton Ave to East State Street	2.92-3.38	The project will consist of milling 2-3" from the existing roadway surface and resurfacing to restore pavement	\$0.198	\$0.198	ARRA - STP-STU	Construction	Local System Support	Trenton	Mercer	FSD09515	DVRPC
	Mercer Pavement -Nottingham Way from Clinton Ave to East State Street	0-.40	The project will consist of milling 2-3" from the existing roadway surface and resurfacing to restore pavement	\$0.225	\$0.225	ARRA - STP-STU	Construction	Local System Support	Hamilton	Mercer	FSD09516	DVRPC
	Mercer Pavement -Province Line Rd from Quaker Bridge Rd to Del-Raritan Canal	0-.33	The project will consist of milling 2-3" from the existing roadway surface and resurfacing to restore pavement	\$0.230	\$0.230	ARRA - STP-STU	Construction	Local System Support	Lawrence	Mercer	FSD09517	DVRPC
	Mercer County Pavement Marking Enhancements	Various	Pavement Markings	\$0.200	\$0.200	ARRA - STP-STU	Construction	Local System Support	Various	Mercer	FSD09519	DVRPC
	City of Camden Resurfacing -Phase 3	Various	This project involves the milling and resurfacing of six streets and the construction of one street. This work involves the construction of curb and sidewalks, drainage items and curb ramps. Euclid Avenue - Haddon Avenue to Kaighn Avenue, Erie Street - Point Street to North 9th Street, North 21st Street - Harrison Avenue to River Road, Cambridge Street - Harrison Avenue to River Road, North 3rd Street- Birch Street to State Street, North 4th Street - Elm Street to State Street Construction of Cleveland Avenue - North 30th Street to North 34th Street	\$2.765	\$2.765	ARRA - STP-STU	Construction	Local System Support	Camden	Camden	FSD09521	DVRPC
	Camden County Guiderail Replacement Program	Various	Upgrade 40,000 LF of guardrail on Camden County roadways.	\$4.000	\$4.000	ARRA - STP-STU	Construction	Local System Support	Various	Camden	FSD09533	DVRPC
	City of Trenton - Broad Street - Ferry to Lafayette	42.26-42.71	The project consists of milling of 3" of existing paving to concrete base & resurfacing with 3" of HMA. The paving width will be the same as exists between existing curbs. Inlet castings will be changed to comply with present NJDEP Regulations. The existing roadway is in very poor condition and Broad Street is a major North-South artery through Trenton and is also NJ Route 206.	\$1.000	\$1.000	ARRA - STP-STU	Construction	Local System Support	Trenton	Mercer	FSD09522	DVRPC
	City of Trenton - ADA Ramps	Various	The City of Trenton is under court order to install ADA compliant ramps at all intersections in the City. To date, the City has installed over 1,000 ramps and has approximately 1,200 remaining. This project will provide for the installation of 145 ramps at various locations in Trenton. The project includes the removal of curb and sidewalk at each intersection, installing new curbing with ADA depression and replacing the sidewalk and the detectable warning surface, repaving the gutter to meet the ADA requirements.	\$0.500	\$0.500	ARRA - STP-STU	Construction	Local System Support	Trenton	Mercer	FSD09523	DVRPC



New Jersey Department of Transportation
FY 2009-2018 STIP Addendum
American Recovery and Reinvestment Act
State and Local Projects
 (\$ in Millions)



State Route #	Project	MP to MP	Description	Total Cost (in millions)	ARRA Programmed Federal Share	ARRA Fund Category	Phase of Work	SCIS Category	Municipalities	County	STIP Reference #	MPO
	City of Trenton - Bellevue Avenue. Calhoun to Willow.	1.09-1.30	The project consists of milling the existing paving to concrete base 3"± and resurfacing with 3" of HMA. The paving width will be the same as exists. The paving is in poor condition and Bellevue Ave. is a bus route and major access to Mercer Hospital located west of the project area on Bellevue Ave. The project is the third phase of Bellevue Avenue resurfacing.	\$0.420	\$0.420	ARRA - STP-STU	Construction	Local System Support	Trenton	Mercer	FSD09524	DVRPC



New Jersey Department of Transportation
FY 2009-2018 STIP Addendum
American Recovery and Reinvestment Act
State and Local Projects
 (\$ in Millions)



State Route #	Project	MP to MP	Description	Total Cost (in millions)	ARRA Programmed Federal Share	ARRA Fund Category	Phase of Work	SCIS Category	Municipalities	County	STIP Reference #	MPO
---------------	---------	----------	-------------	--------------------------	-------------------------------	--------------------	---------------	---------------	----------------	--------	------------------	-----

NJTPA Local Projects

	Court Street Bridge over the Hackensack River, Bergen County	NA	This project provides for the rehabilitation of the Court Street Bridge over the Hackensack River in Essex County. The existing bridge is a center-bearing swing span Warren thru truss bridge with two steel girder approach spans supported on a concrete structure. The overall length of the structure is 316 feet. The bridge will be dismantled, and the approach spans will be reconstructed using concrete box beams. The mechanical and electrical equipment will be completely rehabilitated or replaced. The sufficiency rating is 1.	\$16.788	\$16.788	ARRA - STP- NJ	Construction	Local System Support	Bogota Hackensack	Bergen	FS09393	NJTPA
	Resurfacing - Essex County	NA	This project will entail milling and resurfacing of county roadways. Additional work items would include any required resetting and/or reconstruction of manholes, inlets, replacement of inlet curb pieces and installation of bicycle safe inlet grates, replacement of existing traffic signal loop detectors, crosswalk improvements such as installation of barrier free access ramps and detectable warning surface plates, sidewalk and curb restoration, cleaning of existing drainage systems, re-stripping of traffic lines, stop bars and pedestrian crossings. These roadways are rated with poor surface pavement conditions and requires immediate roadway resurfacing	\$9.876	\$9.876	ARRA - STP- NJ	Construction	Local System Support	Various	Essex	FSN09455	NJTPA
	Baldwin Avenue Project, Hudson County	NA	The existing road will be realigned and widened to accommodate increased traffic due to improvements along the waterfront.	\$1.000	\$1.000	ARRA - STP- NJ	Construction	Local System Support	Weehawken	Hudson	98551	NJTPA
	Union City Street Improvements and Traffic Signal Replacement, Hudson County	NA	This project will provide for improvements to Summit Ave. between 7th and 11th Streets. The improvements will include replacement of concrete curbing and sidewalks, a stamped colored concrete accent strip, installation of shade trees, milling and paving of the roadway, and replacement of the pavement markings and line striping. The project may also include the installation of imprinted crosswalks.	\$1.000	\$1.000	ARRA - STP- NJ	Construction	Local System Support	Union City	Hudson	08436	NJTPA
	Improvements to Pedestrian Indications on Route 501, JFK Boulevard, Hudson County	NA	This project provides improvements to pedestrian indications along John F. Kennedy Blvd. East from 18th Street to 27th Street in North Bergen Township and the City of Union City. All existing pedestrian indications will be replaced with incandescent-look countdown LED units. The roadway is about 60 feet wide and has four traffic lanes with parking on both sides and no median. The length of the project is approximately 2,600 LF and contains about 9 intersections.	\$0.070	\$0.070	ARRA - STP- NJ	Construction	Local System Support	North Bergen Union City	Hudson	FSN09462	NJTPA
	Improvements to Pedestrian Indications on Route 681, Paterson Plank Road, Hudson County	NA	This project provides improvements to pedestrian indications along John F. Kennedy Blvd. East from the Manhattan Avenue/South Wing Viaduct to Columbia Avenue in the City of Jersey City and North Bergen Township. All existing pedestrian indications will be replaced with incandescent-look countdown LED units. The roadway is about 35 feet wide and has two traffic lanes with parking on both sides and no median. The length of the project is approximately 9,500 LF and contains about 11 intersections.	\$0.110	\$0.110	ARRA - STP- NJ	Construction	Local System Support	Jersey City North Bergen	Hudson	FSN09463	NJTPA



New Jersey Department of Transportation
FY 2009-2018 STIP Addendum
American Recovery and Reinvestment Act
State and Local Projects
 (\$ in Millions)



State Route #	Project	MP to MP	Description	Total Cost (in millions)	ARRA Programmed Federal Share	ARRA Fund Category	Phase of Work	SCIS Category	Municipalities	County	STIP Reference #	MPO
	Improvements to Pedestrian Indications on Route 690 and Route 501 JFK Boulevard, Hudson County	NA	This project provides improvements to pedestrian indications along John F. Kennedy Blvd. East from W. 1st Street to W. 57th Street in the City of Bayonne. All existing pedestrian indications will be replaced with incandescent-look countdown LED units. The roadway is about 60 feet wide and has four traffic lanes with parking on both sides and no median. The length of the project is approximately 19,200 LF and contains about 44 intersections.	\$0.370	\$0.370	ARRA - STP-NJ	Construction	Local System Support	Bayonne	Hudson	FSN09464	NJTPA
	Improvements to Pedestrian Indications on Routes 693, 505 and 677 JFK Boulevard East (Baldwin to Woodcliff), Hudson County	NA	This project provides improvements to pedestrian indications along John F. Kennedy Blvd. East from the South Marginal Highway through Wall Street / Woodcliff Avenue, in Guttenberg, North Bergen, Weehawken and West New York. All existing pedestrian indications will be replaced with incandescent-look countdown LED units. The roadway is about 50 feet wide and has two traffic lanes with parking on both sides and no median. The length of the project is approximately 17,700 LF and contains about 26 intersections.	\$0.175	\$0.175	ARRA - STP-NJ	Construction	Local System Support	Guttenberg North Bergen Weehawken	Hudson	FSN09465	NJTPA
	Roadway Resurfacing - Sip Avenue and Newark Avenue, Jersey City	NA	The project includes, the installation of handicapped curb ramps where required, installation of detectable warning surfaces, in-kind replacement of concrete curb and concrete sidewalk where required, replacement of the catch basin cast iron curb pieces with environmentally acceptable catch basin curb pieces, reconstruction of existing catch basins, resetting and/or replacement of castings, installation of bicycle safe grates, milling, resurfacing with Hot Mix Asphalt, and long life traffic striping. The roadway is in fair to poor condition and in need of a resurfacing in order to maintain structural integrity and to avoid costly reconstruction. The road has many cracks, patches, depressions, utility trench repairs and areas of pavement failure.	\$4.558	\$4.558	ARRA - STP-NJ	Construction	Local System Support	Jersey City	Hudson	FSN09467	NJTPA
	Route 501, JFK Boulevard Improvement, Hudson County	NA	Roadway resurfacing of Route 501 JFK Boulevard - Section 17, (W52nd Street to Neptune Avenue). The current condition of the pavement ranges from fair to poor with numerous pavement cracks and rutting from heavy truck traffic. Construction will include complete roadway resurfacing (2" milling and 2" HMA overlay) with traffic stripes and markings. Handicap ramps and Eco-compliant inlet curb pieces will be installed or replaced where necessary. The roadway is an urban minor arterial with a speed limit of 25MPH and runs from north to south through the entire county. The curb to curb width is about 60 feet with parking generally permitted on both sides. The roadway has curb and sidewalks on both sidewalks. The length of the project is about 4,700 LF. Near the Bayonne/Jersey City border, Kennedy Boulevard intersects with the Route 440 connection ramps.	\$0.580	\$0.580	ARRA - STP-NJ	Construction	Local System Support	Bayonne Jersey City	Hudson	FSN09468	NJTPA



New Jersey Department of Transportation
FY 2009-2018 STIP Addendum
American Recovery and Reinvestment Act
State and Local Projects
 (\$ in Millions)



State Route #	Project	MP to MP	Description	Total Cost (in millions)	ARRA Programmed Federal Share	ARRA Fund Category	Phase of Work	SCIS Category	Municipalities	County	STIP Reference #	MPO
	Route 681, Paterson Plank Road Resurfacing, Hudson County	NA	Roadway resurfacing of Route 681 Paterson Plank Road, JFK Boulevard to So App 14th Street. The current condition of the 18 year old pavement ranges from fair to poor with numerous pavement cracks and scaling. Construction will include complete roadway resurfacing (2" milling and 2" HMA overlay) with traffic stripes and markings. Handicap ramps and Eco-compliant inlet curb pieces will be installed or replaced where necessary. The roadway is an urban minor arterial with a speed limit of 25MPH and generally runs from south-east to north-west of the county. The curb to curb width is about 39 feet. In this area Paterson Plank Road has two traffic lanes with parking on both sides. The length of the project is about 3,600 LF. About a third of the project runs through Washington Park (County). The limits for Paterson Plank Road (CR681) Resurfacing are from JF Kennedy Blvd to South Approach to 14th Street Viaduct) Jersey City & Union City.	\$0.250	\$0.250	ARRA - STP- NJ	Construction	Local System Support	Jersey City Union City	Hudson	FSN09473	NJTPA
	Secaucus Resurfacing - Secaucus Rd, Seaview Ave & Paterson Plank Rd		This project will include complete roadway resurfacing (variable depth milling and HMA overlay) with traffic striping, signs and marking along with concrete curb replacement. Handicapped ramps and NJDEP compliant inlet curb heads will be installed or replaced where needed. Additional storm drainage will be added to supplement the existing drainage system.	\$0.932	\$0.932	ARRA - STP- NJ	Construction	Local System Support	Secaucus	Hudson		NJTPA
	Bayonne Resurfacing - Avenue C from 1st St to 18th St		This project will include complete roadway resurfacing (variable depth milling and HMA overlay) with traffic striping, signs and marking along with concrete curb replacement. Handicapped ramps and NJDEP compliant inlet curb heads will be installed or replaced where needed. Additional storm drainage will be added to supplement the existing drainage system.	\$1.293	\$1.293	ARRA - STP- NJ	Construction	Local System Support	Bayonne	Hudson		NJTPA
	Route 678 Secaucus Road Resurfacing		Secaucus Road Construction will include complete roadway resurfacing (2" milling and 2" HMA overlay) with traffic stripes, signs and markings. Handicap ramps and Eco-compliant inlet curb pieces will be installed or replaced where necessary. . The limits are from 300 feet west J F Kennedy Boulevard to County Avenue, Jersey City, North Bergen, Secaucus and Union City. Actual limits of pavement resurfacing will be from 300 feet west of JF Kennedy Boulevard to US Routes 1&9 east project limit and from US Routes 1&9 west project limit to County Avenue. The US Routes 1&9/Secaucus Road interchange (about 1000 LF) will not be paved, since it is recent project and in good condition. Additionally, no work will take place on the NJ Turnpike Bridge along Secaucus Road.	\$0.950	\$0.950	ARRA - STP- NJ	Construction	Local System Support	Towship of North Bergen, City of Union City, City of Jersey City and Town of Secaucus	Hudson	FSN09472	NJTPA
	Route 659 Fish House Road Resurfacing		Fish House Road construction will include complete roadway resurfacing (2" milling and 2" HMA overlay) with traffic stripes, signs and markings. Eco-compliant inlet grates and curb pieces will be installed or replaced where necessary. The limits are from the terminus of ramps to Route 7 to the limit of paving (near PSE&G) from the recent Central Avenue resurfacing project performed by the county in 2008.	\$0.275	\$0.275	ARRA - STP- NJ	Construction	Local System Support	Town of Kearny	Hudson	FSN09470	NJTPA



New Jersey Department of Transportation
FY 2009-2018 STIP Addendum
American Recovery and Reinvestment Act
State and Local Projects
 (\$ in Millions)



State Route #	Project	MP to MP	Description	Total Cost (in millions)	ARRA Programmed Federal Share	ARRA Fund Category	Phase of Work	SCIS Category	Municipalities	County	STIP Reference #	MPO
	Pavement Rehabilitation Program, Hunterdon County	NA	The project will include milling and delaminating existing surface course 2 inches and resurfacing with a 2 inch lift. Minor base course repairs will be made as needed. All existing storm drainage inlets will be modified to conform to current Stormwater requirements. In addition all pavement markings inclusive of the bicycle lanes will be delaminating with long life epoxy traffic paint. Raised pavement markers will be added to center lane striping. All traffic signing will be inspected and replaced as needed.	\$3.720	\$3.720	ARRA - STP-NJ	Construction	Local System Support	Various	Hunterdon	FSN09474	NJTPA
	Guiderail Installation/Replacement Program, Middlesex County	NA	A Countywide evaluation of guiderails along all county routes was performed and reported in an April 2002 final report. The report identified the locations where new guiderails were warranted and existing guiderails were not in conformance with current standards. This project includes safety enhancements such as installation of new guiderail at warranted locations, replacement and/or upgrades to existing guiderail and end treatments as well as approach guiderail, approach guiderail terminals, transitions and bridge rail on county bridges and culverts to meet current standards.	\$6.731	\$6.731	ARRA - STP-NJ	Construction	Local System Support	Various	Middlesex	FSN09476	NJTPA
	Roadway Resurfacing Program, Middlesex County	NA	This project consists of milling and resurfacing various roads in Middlesex County. This is a planned strategy of cost effective treatments to an existing roadway system that preserves the system, retards future deterioration, and maintains or improves the functional condition of the system without increasing structural capacity.	\$7.514	\$7.514	ARRA - STP-NJ	Construction	Local System Support	Various	Middlesex	FSN09440	NJTPA
	Roadway Resurfacing Program, Monmouth County	NA	This program will provide for the rehabilitation of approximately 29 miles of roadways at 11 different sites. Most of the targeted road sections are near or have reached the end of their preferred resurfacing life schedule and are showing signs of deterioration. Work to be performed includes milling, paving targeted sections with hot mix asphalt, installing all necessary long life pavement markings and raised pavement markers, and constructing required public sidewalk ramps. Roadways targeted for rehabilitation include sections of CR 16, CR 18, CR 520, CR 524, CR 527, and CR 537.	\$5.438	\$5.438	ARRA - STP-NJ	Construction	Local System Support	Various	Monmouth	FSN09439	NJTPA
	County Bridge S-31, Priority 1 Structural Steel Repairs, Monmouth County	NA	This project will repair structural steel elements on the Oceanic Bridge (S-31), a 57 span bridge with a double link deck girder bascule span built in 1939 and reconstructed in 1970. This bridge carries County Route 8A (Bingham Avenue – Locust Point Road) over the Navesink River in the Borough of Rumson. The steel components of the bridge are in very poor condition with extensive corrosion, section loss, and fatigue damage. Corrective action will include blast cleaning, painting, cover plate repairs, and the replacement of deteriorated cross-bracing members.	\$1.300	\$1.300	ARRA - STP-NJ	Construction	Local System Support	Rumson	Monmouth	FSN09438	NJTPA



New Jersey Department of Transportation
FY 2009-2018 STIP Addendum
American Recovery and Reinvestment Act
State and Local Projects
 (\$ in Millions)



State Route #	Project	MP to MP	Description	Total Cost (in millions)	ARRA Programmed Federal Share	ARRA Fund Category	Phase of Work	SCIS Category	Municipalities	County	STIP Reference #	MPO
	County Bridge MN-10 Reconstruction and Rehabilitation of Millhurst Dam, Monmouth County	NA	This project will reconstruct the CR-527 (Sweetmans Lane) bridge (MN-10) over Manalapan Brook in Manalapan Township, and the adjacent Millhurst Dam and spillway. The existing roadway is supported by the dam and the bridge, constructed in 1953, passes over its spillway. The existing road fails to meet current standards and the bridge currently has a 10-ton weight limit. This project will widen CR-527 to current standards and realign it to avoid interference with an historic mill building. The earthen embankment dam will be widened to accommodate the new road geometry. The spillway walls will be replaced with a new reinforced concrete structure. A sidewalk will be added.	\$1.946	\$1.946	ARRA - STP- NJ	Construction	Local System Support	Manalapan	Monmouth	FSN09437	NJTPA
	Upgrade of Electrical Components at Signalized Intersections, Monmouth County	NA	This project would upgrade existing signalization equipment at numerous intersections countywide. A number of signalized intersections are operating at a low level of service due to technologically obsolete equipment. This project would upgrade several signal systems with up-to-date electronic components including, but not limited to, phase controllers, menu driven voltage monitors, battery back-up systems, camera detection systems, vehicular signal indications, pedestrian signal indications, pedestrian push button assemblies, preemption equipment and ancillary electrical components.	\$3.000	\$3.000	ARRA - STP- NJ	Construction	Local System Support	Various	Monmouth	FSN09436	NJTPA
	Chester Branch Railroad Rehabilitation, Morris County	NA	This project will rehabilitate four miles of the Chester Branch Railroad. The present condition of the track has caused numerous derailments, negatively impacting the line's customers and compromising the safety of train crews. This project will include track change out, tie replacements, new ballasts, 3 #8 switches-complete, 3 #8 switch timbers, 1 #8 turnout, surfacing of the entire right of way, new runarounds and turnouts, brush cutting, wood chipping, and tie removal.	\$5.800	\$5.800	ARRA - STP- NJ	Construction	Local System Support	Roxbury Township	Morris	FSN09435	NJTPA
	Intersection Improvements, Morris County	NA	This project will improve two intersections in the Township of East Hanover: CR-632 (Ridgedale Avenue) at Deforest Avenue and Ridgedale Avenue at Troy Road. Faulty and failing signal equipment is causing delays at these intersections. Proposed improvements at the Deforest Avenue intersection include a total replacement of the traffic signal equipment, the addition of a right turn lane from northbound Ridgedale onto Deforest, new pavement markings to allow for opposing left turn lanes on Ridgedale, wheelchair accessible curb ramps (with NJDOT-approved detectable warning devices), pedestrian push buttons and countdown pedestrian signals. Proposed improvements at the Troy Road intersection include a partial replacement of signal equipment.	\$0.350	\$0.350	ARRA - STP- NJ	Construction	Local System Support	East Hanover	Morris	FSN09434	NJTPA
	Roadway Resurfacing Program, Morris County	NA	The milling and resurfacing projects in Morris County consist of 2" pavement milling, 2" resurfacing, drainage repair, traffic stripes and loop detector replacement due to deterioration of the existing pavement caused by heavy traffic and environmental conditions. All work will be done within the limits of the existing pavement and no widening will be done.	\$2.379	\$2.379	ARRA - STP- NJ	Construction	Local System Support	Various	Morris	FSN09433	NJTPA



New Jersey Department of Transportation
FY 2009-2018 STIP Addendum
American Recovery and Reinvestment Act
State and Local Projects
 (\$ in Millions)



State Route #	Project	MP to MP	Description	Total Cost (in millions)	ARRA Programmed Federal Share	ARRA Fund Category	Phase of Work	SCIS Category	Municipalities	County	STIP Reference #	MPO
	Traffic Signal Improvements-Littleton Road/Parsippany Boulevard, Morris County	NA	The project is at the intersection of Littleton Road/Parsippany Boulevard and Parsippany Road(CR511)/ Littleton Road (CR 630). This project consists of the partial replacement of out dated traffic signal equipment in order to eliminate continual delays caused at the intersection due to faulty and failing signal equipment and a poor lane configuration. The existing loop detector system will be replaced with a video detection system. The project includes a minor widening to the Littleton Road (Legis Route 202) eastbound approach to accommodate right turn movements in a separate lane. Additionally the project will replace pavement markings on the eastbound and westbound approaches to the intersection. Curb ramps will be installed on the southwest corner of the intersection.	\$0.200	\$0.200	ARRA - STP- NJ	Construction	Local System Support	Parsippany-Troy Hills	Morris	FSN09432	NJTPA
	Traffic Signal Improvements-West Hanover Avenue and Burnham Road, Morris County	NA	This project is at the intersection of West Hanover Avenue and Burnham Road - Stiles Avenue and consists of the total replacement of out dated traffic signal equipment in order to eliminate continual delays. The existing loop detector system will be replaced with a video detection system. An emergency pre-emption device will be included for the adjacent fire house, which will expedite emergency fire calls. Minor changes are being made to the corner radii, including curb ramps. Other improvements include restriping, new energy efficient signal heads, new wiring, poles, emergency back-up system, and pedestrian safety improvements.	\$0.200	\$0.200	ARRA - STP- NJ	Construction	Local System Support	Morris Plains	Morris	FSN09431	NJTPA
	Roadway Resurfacing Program, City of Newark	NA	This program entails the construction of roadway improvements and resurfacing at various locations throughout Newark. Sidewalk, curbing and minor drainage improvements will take place along the project limits as deemed required. Handicap ramp repair and replacement, as needed, will be include in this project. No right-of-way acquisition is anticipated for this project.	\$4.894	\$4.894	ARRA - STP- NJ	Construction	Local System Support	Newark	Essex	FSN09459	NJTPA
	Traffic Signal Improvements-Wilson Avenue and Rome Street, City of Newark	NA	This traffic signalization project will address the continuing issue excessive delays and congestion in this area of Newark. The project will provide for updated traffic signals at the intersection of Wilson Avenue and Rome/Jabez Street as well as the replacement of traffic controllers and the development of new signal timing plans.	\$0.300	\$0.300	ARRA - STP- NJ	Construction	Local System Support	Newark	Essex	FSN09460	NJTPA
	Beaver Dam Bridge Painting, Ocean County	NA	This project consists of the painting of the Beaver Dam Bridge in order to halt deterioration and maintain structural integrity. The structure needs to be blasted clean to remove scale, rust and pitting. The hydraulic drawspan bridge is comprised of two main steel girders, steel floor beams and steel elements for bracing.	\$0.575	\$0.575	ARRA - STP- NJ	Construction	Local System Support	Point Pleasant Brick	Ocean	FSN09430	NJTPA



New Jersey Department of Transportation
FY 2009-2018 STIP Addendum
American Recovery and Reinvestment Act
State and Local Projects
 (\$ in Millions)



State Route #	Project	MP to MP	Description	Total Cost (in millions)	ARRA Programmed Federal Share	ARRA Fund Category	Phase of Work	SCIS Category	Municipalities	County	STIP Reference #	MPO
	Roadway Resurfacing Program, Ocean County	NA	This pavement overlay project entails a 2 1/2" mill and 2 1/2" Superpave Hot Mix Asphalt resurfacing of various roadways in Ocean County. This resurfacing work is necessary to remove existing surface cracking and pavement oxidation. This work will extend and preserve the pavement life to prevent costly future full reconstruction work. All construction will remain within existing curbs or edge of pavement. This road is currently in compliance with AASHTO design standards and has minimum 8' shoulder lanes. Incidental construction shall include pavement striping, upgrading guiderail terminal end treatments to meet current standards, upgrading stream flow stormwater grates to bicycle safe stormwater grates and installing 'eco' retro fit plates on curb inlets currently lacking such features in order for all inlet structures to comply with the current NJDEP stormwater regulations.	\$2.646	\$2.646	ARRA - STP-NJ	Construction	Local System Support	Various	Ocean	FSN09428	NJTPA
	Reconstruction of Route 539 at the New Fort Dix Entrance, Ocean County	NA	The project will widen and resurface/reconstruct 1500 feet of Ocean County Route 539 to provide left turn lanes and right turn acceleration/deceleration lanes to the new Fort Dix entrance for the Consolidated Logistics and Training Facility for the NJ Army National Guard, Lakehurst Naval Air Engineering Station.	\$0.150	\$0.150	ARRA - STP-NJ	Construction	Local System Support	Jackson Twp. Plumsted Twp.	Ocean	09300	NJTPA
	Replacement of Beach Boulevard Bridge, Ocean County	NA	The Beach Blvd. Bridge #1 is a five span, timber pile supported, voided box beam bridge built in 1967. The voided box beam superstructure is showing signs of deterioration, thru longitudinal cracks and rust stains from interior reinforcement. The overall rating of the structure is FAIR due the deteriorating superstructure, however, the bridge lane width is restricted to keep live load off beams that have failed. The proposed replacement will be concrete, the design would differ from the original in that the five spans would be reduced to four spans and there would be only three pile bents within the waterway. These three pile bents would be concrete filled pipe piles, rather than timber. Replacement will be on the existing alignment.	\$5.406	\$5.406	ARRA - STP-NJ	Construction	Local System Support	Lacey	Ocean	FSN09419	NJTPA
	Safety Upgrade Replacement of Bridge Guiderail End Treatments at 82 Bridges, Ocean County	NA	This project will upgrade the existing end treatments of the guide rails on 82 bridges to extruder end sections. This will bring each bridge with guide rail to Federal standards.	\$0.925	\$0.925	ARRA - STP-NJ	Construction	Local System Support	Various	Ocean	FSN09564	NJTPA
	Roadway Resurfacing Program, Passaic County	NA	The Resurfacing Project consists of the milling of existing 2-inches of existing asphalt surface course, and replacement with 2-inches of new Hot Asphalt Riding Surface Course; staying within the existing pavement limits. Some roadways will not require milling, only a 2-inch Hot Mix Surface Course overlay. Associated work includes resetting of existing manholes and inlets; along with replacing all obliterated Pavement Lines and Markings, with long-life Thermoplastic material. In addition, work will include replacing and retrofitting existing inlet castings with upgraded head castings to meet the NJDEP storm water restricted castings; along with new bicycle safe riding grates.	\$9.287	\$9.287	ARRA - STP-NJ	Construction	Local System Support	Various	Passaic	FSN09417	NJTPA



New Jersey Department of Transportation
FY 2009-2018 STIP Addendum
American Recovery and Reinvestment Act
State and Local Projects
 (\$ in Millions)



State Route #	Project	MP to MP	Description	Total Cost (in millions)	ARRA Programmed Federal Share	ARRA Fund Category	Phase of Work	SCIS Category	Municipalities	County	STIP Reference #	MPO
	Roadway Resurfacing Program, Somerset County	NA	This project provides construction and inspection of various County roads which are located throughout Somerset County. Those roads are in need of resurfacing due to their pavement condition. This work will consist of milling 2 to 6 inches of the existing roadway widths and resurfacing with HMA19M64 base course 0 to 4 inches thick and HMA 9.5M64 Surface Course 2" thick. Existing curbing will also be replaced in kind as needed and roadways restriped. The existing roadway profiles will be maintained. This project will extend the life of the roadway and delay the need for complete reconstruction.	\$5.649	\$5.649	ARRA - STP- NJ	Construction	Local System Support	Various	Somerset	FSN09416	NJTPA
	Route 519, Roadway Rehabilitation, Sussex County	MP 67.83 - 71.37	This resurfacing project involves reclamation of the existing base course and subgrade, providing a stronger subgrade, and replacing the base course and surface course with new material. Long life pavement markings and reflective pavement markings will also be part of this project. Existing signs will be upgraded as part of this project.	\$0.819	\$0.819	ARRA - STP- NJ	Construction	Local System Support	Hampton Twp Frankford	Sussex	FSN09414	NJTPA
	Replacement of Bridge Q-09, Sussex County	NA	This is a bridge replacement project for Bridge Q-09 carrying CR 620 (Main Street) over Glen Brook in Sparta Township. A temporary structure has been in place since the original bridge was destroyed in 2000 flood. The replacement design is complete and all permits have been approved and acquired, and a Categorical Exclusion Document (CED) is also approved for this project.	\$0.600	\$0.600	ARRA - STP- NJ	Construction	Local System Support	Sparta	Sussex	FSN09413	NJTPA
	Replacement of Bridge Q-11, Sussex County	NA	This is a bridge replacement project to carry Glen Road (CR 620) over Sparta Glen Brook. A temporary structure has been in place since 2000 when bridge Q-11 was destroyed. The replacement design is complete. All permits have been approved and acquired. The Categorical Exclusion Document (CED) is also approved for this project.	\$1.200	\$1.200	ARRA - STP- NJ	Construction	Local System Support	Sparta	Sussex	FSN09412	NJTPA
	Route 616, Roadway Resurfacing, Sussex County	MP 0 - 5.10	This resurfacing project will mill 1 1/2" of asphalt and replace 2" of asphalt. Long life pavement markings and reflective pavement markings will also be part of this project. Existing signs will be upgraded.	\$1.045	\$1.045	ARRA - STP- NJ	Construction	Local System Support	Newton Andover Twp. Sparta	Sussex	FSN09410	NJTPA
	Route 620, Microresurfacing, Sussex County	MP 01.00 - 01.93	This is a microsurfacing project. It will extend the service life of the existing pavement and provide a highly skid-resistant surface that will serve to cut down on vehicles leaving the roadway and crossing lanes, a condition found to be present at this location. Long life pavement markings and reflective pavement markings will also be part of this project. Existing signs will be upgraded as part of this project.	\$0.056	\$0.056	ARRA - STP- NJ	Construction	Local System Support	Sparta	Sussex	FSN09409	NJTPA



New Jersey Department of Transportation
FY 2009-2018 STIP Addendum
American Recovery and Reinvestment Act
State and Local Projects
 (\$ in Millions)



State Route #	Project	MP to MP	Description	Total Cost (in millions)	ARRA Programmed Federal Share	ARRA Fund Category	Phase of Work	SCIS Category	Municipalities	County	STIP Reference #	MPO
	Intersection Improvements, Springfield Avenue, Union County	NA	<p>This project will provide for upgrading two signalized intersections along Springfield Avenue (CR615) in the Township of Cranford at the intersection of Springfield Avenue and N. Union Avenue, and the intersection of Springfield Avenue and Orange Avenue. The project will involve the replacement of antiquated signal equipment, including poles, mast arms, LED indicators, countdown pedestrian indicators, and battery backup systems, as well as upgrading all regulatory signage and striping. The project will also include safety enhancements for pedestrian, bicycle and auto traffic, replacement/repair of handicap ramps, as well as timing of lights and coordination with nearby intersections/corridors. All work will be in accordance with current MUTCD standards.</p> <p>This project has a visual impact on the north Cranford Historic District, the Rahway River Historic District and the Crane House.</p>	\$0.510	\$0.510	ARRA - STP- NJ	Construction	Local System Support	Cranford	Union	FSN09406	NJTPA
	Roadway Improvements and Handicap Ramps, Union County	NA	<p>This project will provide milling, resurfacing and handicap ramp construction of approximately 12.6 miles of various Union County roads in Berkeley Heights, Elizabeth, Kenilworth, Linden, Mountainside, Rahway, Roselle Park, Scotch Plains, Springfield, Summit, Union, Watchung (Somerset County), and Westfield. The project will involve pavement repair (2" milling and 2" resurfacing), handicap ramp replacement/repair, all regulatory street name signage upgrades, traffic striping replacement, as well as State mandated stormwater management upgrades on existing inlets. All work will be in accordance with current MUTCD standards.</p> <p>This project passes in front of the Borough Funeral Home, Springfield & Morris Avenue, Summit, and it passes through Echo Lake Park, Mountainside, both on the historic register.</p>	\$4.588	\$4.588	ARRA - STP- NJ	Construction	Local System Support	Various	Union	FSN09405	NJTPA



New Jersey Department of Transportation
FY 2009-2018 STIP Addendum
American Recovery and Reinvestment Act
State and Local Projects
 (\$ in Millions)



State Route #	Project	MP to MP	Description	Total Cost (in millions)	ARRA Programmed Federal Share	ARRA Fund Category	Phase of Work	SCIS Category	Municipalities	County	STIP Reference #	MPO
	Terrill Road Corridor Signalization-Somerset County Line to Martine Avenue, Union County	NA	This project will provide for the upgrading of seven signalized intersections in the City of Plainfield, Township of Scotch Plains, and Borough of Fanwood at the intersection of Terrill Road (CR611) and Front Street (CR620), the intersection of Terrill Road and 2nd Street, the intersection of Terrill Road and Midway Avenue (CR610)/3rd Street, the intersection of Terrill Road and South Avenue (NJSH 28), the intersection of Terrill Road and E. 7th Street/LaGrande Avenue (CR601), the intersection of Terrill Road and Cooper Road, as well as the intersection of Raritan Road (CR611) and Martine Avenue (CR655). The project will involve replacement of antiquated signal equipment as well as upgrading all regulatory signage and striping. The project will also include safety enhancements for pedestrian, bicycle and auto traffic, replacement/repair of handicap ramps, as well as timing and coordination of lights along the corridor. All work will be in accordance with current MUTCD standards. 850 Terrill Road, located 380' south of the intersection of Terrill & LaGrande is registered as an Historic Property.	\$1.420	\$1.420	ARRA - STP- NJ	Construction	Local System Support	Plainfield Scotch Plains Fanwood	Union	FSN09403	NJTPA
	Intersection Improvements, Union County	NA	This project will provide for the upgrading of various signalized intersections in the City of Elizabeth at the intersection of S. Broad Street (CR623) and Sumner Street, the intersection of S. Broad Street (CR623) and South Street, the intersection of Pearl Street (CR614) and Washington Avenue, the intersection of N. Broad Street (CR623) and Wilder Street, the intersection of W. Grand Street (CR610) and Grove Street (CR614), and the intersection of Magie Avenue (CR618) and Monmouth Avenue. The project will involve replacement of antiquated signal equipment, including poles, mast arms, LED indicators, countdown pedestrian indicators, and battery backup systems, as well as all regulatory signage and striping upgrades. The project will also include safety enhancements for pedestrian, bicycle and auto traffic, handicap ramps replacement/repair, timing of and coordination lights with nearby intersections/corridors. All work will be in accordance with current MUTCD standards.	\$2.530	\$2.530	ARRA - STP- NJ	Construction	Local System Support	Elizabeth	Union	FSN09401	NJTPA



New Jersey Department of Transportation
FY 2009-2018 STIP Addendum
American Recovery and Reinvestment Act
State and Local Projects
 (\$ in Millions)



State Route #	Project	MP to MP	Description	Total Cost (in millions)	ARRA Programmed Federal Share	ARRA Fund Category	Phase of Work	SCIS Category	Municipalities	County	STIP Reference #	MPO
	Park Avenue Corridor Improvements, Union County	NA	This project will provide for upgrading of three signalized intersections along Park Avenue (CR531) in the City of Plainfield, at the intersection of Park Avenue and South End Parkway, the intersection of Park Avenue and Randolph Road, the intersection of Park Avenue and Ninth Street/Prospect Street, and one minor upgrade at the intersection of Park Avenue and Eighth Street only for corridor continuity. The project will involve replacement of antiquated signal equipment as well as upgrading of all regulatory signage and striping. The islands in the intersection of Park Avenue & Ninth Street/Prospect Street will be eliminated. The project will also include safety enhancements for pedestrian, bicycle and auto traffic, replacement/repair of handicap ramps, as well as timing and coordination of lights along the corridor from South End Parkway to Seventh Street. All work will be in accordance with current MUTCD standards. This project impacts the Van Wyck Brook Historic District, the Crescent Area Historic District, and the Orville Taylor Waring House, 900 Park Avenue.	\$0.875	\$0.875	ARRA - STP- NJ	Construction	Local System Support	Plainfield	Union	FSN09402	NJTPA
	Route 519, Roadway Improvements, Warren County	NA	This project will provide pavement repair and resurfacing on CR 519 which is a major collector road on the Warren County road system. Traffic volumes on this roadway exceed 10,000 vehicles per day with a high percentage of truck traffic. The high volume of traffic and heavy trucks have caused ruts and cracking in the pavement surface. Correction of these conditions is needed to provide a safe riding surface for the general public. The proposed project will include milling the existing pavement to a depth of 4 inches. The project will restore the pavement to the original design cross section and profile. There will be no regrading of roadside berms or slopes. Minor restoration work along the road edge will be performed as necessary.	\$3.720	\$3.720	ARRA - STP- NJ	Construction	Local System Support	Harmony White	Warren	FSN09397	NJTPA